DS Environmental CONSULTING

"The trusted choice for your environmental & industrial hygiene needs."

LEAD BASED PAINT INSPECTION REPORT

275 Holbrook St, Erie, Colorado

PRESENTED TO:	INSPECTED BY:	PROJECT DETAILS:
Mr. Mark Rockwell 303-564-5016 markr@rocktonsoftware.com	Mr. Chris Lehman DS Environmental Cell: (720) 369-6609	DS Job Number: 24133 Date of Inspection: June 20, 2022

Front Range 7555 W 10th Ave
Suite A, Lakewood, CO 80214

Mountains PO Box 6864
Avon, CO 81620

Western Slope PO Box 3793
Aspen, CO 81612

Web dsconsultinginc.com

Direct (303) 286-9094

Fax (303) 986-0121

Table of Contents

1.0 Introduction

2.0 Definitions

3.0 Scope of Work

4.0 Inspector & Firm Certifications

5.0 Data Interpretation

6.0 Overview of Findings

7.0 Equipment Information

8.0 Inspection & Testing Procedures

9.0 Conclusion & Recommendations

10.0 Disclaimer & Limitations

11.0 Copyright Notice

APPENDIX A XRF Data Table

APPENDIX B Inspector & Firm Certificates

1.0 Introduction

Mr. Chris Lehman with DS Environmental Consulting (DS) performed a limited-scope, lead-based paint (LBP) inspection and performed in situ X-Ray Florescence (XRF) testing to determine the presence of LBP on select painted building components within the residence detailed on the cover page of this report.

The purpose of the limited-scope inspection was to identify any LBP present on the building components, as defined by the client, that may be impacted by renovation activities. XRF testing was conducted on the main level wall, ceiling and trim. LBP was not found on the tested components.

Table 1 and Table 2 in Section 6.0 further details the materials that contain LBP and those that do not. The full table (Table 3), including all XRF readings, can be found in Appendix A.

2.0 Definitions

Room Equivalent is an identifiable part of a residence, such as a room, a house exterior, a foyer, staircase, hallway or an exterior area.

Lead-based Paint (LBP) is any paint having concentrations of lead greater than 1.0 mg/cm^2, which is also Colorado's action level.

Limited-scope means the extent of the inspection and XRF testing included in this report was limited to a subset of the entire residence, was not a lead hazard assessment, and was not a full-building inspection. No water, air, dust or soil samples were collected or analyzed to determine the respective lead concentrations.

Paint is any liquid mixture, usually of solid pigment in a liquid form, used as a decorative or protective coating. This includes, but is not limited to, primer, lacquer, polyurethane, wood stain, etc.

X-Ray Florescence (XRF) is a non-destructive analytical technique used to determine the elemental composition of materials. XRF analyzers determine the chemistry of a sample by measuring the fluorescent (or secondary) X-ray emitted from a sample when it is excited by a primary X-ray source.

3.0 Scope of Work

The scope of the limited LBP inspection was limited to specific areas of the building defined by the client. The remaining areas within the building, garage or any out-building on the property were not included in the scope of the inspection. The limited LBP inspection did not constitute a full building inspection or hazard assessment. Additionally, there may be other components in other parts of the building that contain LBP, which were not included in the scope of this inspection and sampling.

4.0 Certifications

Mr. Lehman is a Colorado State Certified LBP Inspector; having EPA Accreditation #24948. DS Environmental Consulting is a Colorado State Certified Lead Evaluation Firm, license #16918. Mr. Lehman is certified to operate the RMD LPA-1 and Heuresis Pb200i XRF Lead Paint Spectrum Analyzer by the manufacturer (see Appendix B for certificates).

5.0 Data Interpretation

When evaluating the information included in this report, Wall "A" in each room is the wall where the main front entrance door to the home is located (or aligned with the street). While facing Wall "A" and going clockwise, Wall "B" will always be to the right, Wall "C" directly to the rear and Wall "D" to the left. Ceilings and floors are designated with an asterisk.

If a component, i.e. baseboard, window sill, or door jamb, contains LBP in any room equivalent, then all other components that are similar in color, substrate and painting history can be assumed to be positive as well with no additional testing, regardless of their location in the structure; however, this extrapolation cannot be made the same with negative components. If a component is negative for LBP, only the components in that room equivalent can be assumed negative, additional testing must be done to similar components in each room equivalent.

All walls shall be tested in room equivalents with four or less walls and a minimum of four different walls in room equivalents with more than four walls for all walls to be determined negative; however, the scope of work for a limited-scope inspection may dictate that not all walls are to be impacted; therefore, not all walls will be tested.

**Please note that due to the limited nature of this inspection, only the materials included in this report, in the locations identified, have been tested and no assumptions have been made to the lead-content of similar components in other areas. All inaccessible areas are assumed to be positive, even though they were not able to be tested. These areas may not be listed in this report.

6.0 Inspection, Sampling & Analytical Procedures

Table 1: Components that Contain LBP

No tested components were found to contain LBP

Table 2: Components that Do Not Contain LBP

Read No.	Room/Area	Wall	Structure	Paint Cond	Substrate	Paint Color	Lead (mg/cm^2)	Result
1	Kitchen	B	Wall	Intact	Drywall	White	0.2	Neg
2	Kitchen	*	Ceiling	Intact	Drywall	White	0.2	Neg
3	Kitchen	C	Trim	Intact	Wood	Black	0.0	Neg
4	Kitchen	D	Cabinets	Intact	Wood	Black	0.0	Neg
5	Kitchen	D	Cabinets	Intact	Wood	White	0.0	Neg
6	Living Room	D	Wall	Intact	Drywall	White	0.2	Neg
7	Living Room	*	Ceiling	Intact	Fiberboard	White	0.2	Neg
8	Living Room	*	Ceiling	Intact	Fiberboard	Beige	0.1	Neg
9	Living Room	*	Ceiling	Intact	Fiberboard	Pink	0.2	Neg
10	Living Room	D	Trim	Intact	Wood	Grey	0.2	Neg
11	Kitchen	D	Window Sill	Intact	Wood		0.2	Neg

12	Entry Foyer	A	Wall	Intact	Drywall	White	0.2	Neg
13	Entry Foyer	*	Ceiling	Intact	Drywall	White	0.2	Neg
14	Entry Foyer	A	Trim	Intact	Wood	White	0.1	Neg
15	Entry Foyer	A	Window Sill	Intact	Wood	White	0.2	Neg
16	NE Bedroom	B	Wall	Intact	Drywall	White	0.2	Neg
17	NE Bedroom	*	Ceiling	Intact	Drywall	White	0.2	Neg
18	NE Bedroom	C	Trim	Intact	Wood	White	0.0	Neg
19	NE Bedroom Closet	A	Wall	Intact	Drywall	White	0.2	Neg
20	NE Bedroom Closet	*	Ceiling	Intact	Drywall	White	0.2	Neg
21	NE Bedroom Closet	B	Shelf	Intact	Wood	White	0.1	Neg
22	Hallway	B	Wall	Intact	Drywall	White	0.2	Neg
23	Hallway	*	Ceiling	Intact	Drywall	White	0.2	Neg
24	Hallway	B	Trim	Intact	Wood	White	0.2	Neg
25	Hallway	B	Door	Intact	Wood	White	0.0	Neg
26	Bathroom	B	Wall	Intact	Drywall	Red	0.2	Neg
27	Bathroom	*	Ceiling	Intact	Drywall	Red	0.2	Neg
28	Bathroom	A	Cabinets	Intact	Wood	Red	0.1	Neg
29	Bathroom	B	Window Sill	Intact	Wood	Red	0.2	Neg
30	Bathroom	B	Trim	Intact	Wood	Red	0.2	Neg
31	NW Bedroom	C	Wall	Intact	Drywall	White	0.2	Neg
32	NW Bedroom	*	Ceiling	Intact	Drywall	White	0.2	Neg
33	NW Bedroom	C	Window Sill	Poor	Wood	White	0.2	Neg
34	NW Bedroom	D	Trim	Intact	Wood	White	0.1	Neg
35	NW Bedroom Closet	D	Wall	Intact	Drywall	White	0.2	Neg
36	NW Bedroom Closet	*	Ceiling	Intact	Drywall	White	0.2	Neg
37	NW Bedroom Closet	D	Shelf	Intact	Wood	White	0.2	Neg
38	SE Bedroom	C	Wall	Intact	Drywall	Purple	0.0	Neg
39	SE Bedroom	*	Ceiling	Intact	Drywall	Purple	0.2	Neg
40	SE Bedroom	D	Trim	Intact	Wood	Purple	0.2	Neg
41	SE Bedroom Closet	B	Door	Intact	Wood	Purple	0.1	Neg
42	SE Bedroom Closet	B	Wall	Intact	Drywall	White	0.2	Neg
43	SE Bedroom Closet	*	Ceiling	Intact	Drywall	White	0.2	Neg
44	SE Bedroom Closet	B	Shelf	Intact	Wood	White	0.2	Neg
45	East Entry Foyer	C	Wall	Intact	Drywall	White	0.0	Neg
46	East Entry Foyer	*	Ceiling	Intact	Drywall	White	0.2	Neg
47	East Entry Foyer	B	Trim	Intact	Wood	White	0.2	Neg
48	East Entry Foyer	C	Door/Trim	Intact	Wood	White	0.1	Neg

7.0 Equipment Information

LBP concentrations were obtained using a RMD Model LPA-1 or a Heuresis Pb200i XRF Lead Paint Spectrum Analyzer, which is approved by the U.S. Environmental Protection Agency (EPA) and the U.S. Department of Housing and Urban Development (HUD) to determine the concentration of lead in paint.

The XRF was calibrated according to the manufacturer's Performance Characteristic Sheet (PCS). The XRF was calibrated using the calibration standard block of known 1.0 mg/cm^2 lead content as well as a standard block of known 0.0 mg/cm^2 lead content. Three (3) calibration reading of each block were taken before the inspection began as well as after the inspection was completed.

8.0 Inspection & Testing Procedures

The LBP inspection and XRF testing were conducted by a State of Colorado accredited LBP Inspector qualified by experience, education, and training in approved LBP testing techniques. These procedures call for the visual inspection of the areas of concern and the collection of XRF readings for lead concentrations.

This inspection was performed in accordance with the U.S. Environmental Protection Agency (EPA) and the U.S. Department of Housing and Urban Development (HUD) guidelines for lead-hazard inspections, as well as the State of Colorado Air Quality Control Commission Regulation No. 19 for the Control of Lead Hazards. The EPA's 40 CFR Part 745 Final Rule (January 5, 2001) set standards for the identification of dangerous levels of lead. The standards identify when lead-based paint, lead-contaminated dust, and lead-contaminated soil are hazards. It also establishes residential dust clean-up levels (post-abatement clearance levels) and set dust and soil sampling requirements. The lead-based paint readings were collected by XRF analyzation for the purpose of determining lead concentrations as mg/cm^2.

9.0 Conclusions & Recommendations

Concentrations of lead in paint higher than the State of Colorado regulatory levels were not identified; therefore, no further "lead safe" work practices are required when disturbing, removing or impacting the tested components. Additional testing is required if new materials are discovered or the scope of work changes.

10.0 Disclaimer & Limitations

This limited-scope inspection does not constitute a comprehensive lead-based paint inspection or full lead-hazard assessment. Other areas not tested and conditions existing outside this scope of work may contain lead concentrations above the regulatory action levels. Consequently, to determine whether or not lead-based paint exists within other areas of the building, a full lead-based paint inspection must occur.

11.0 Copyright Notice

© DS Environmental 2022. All Rights Reserved. This document contains material protected under Federal Copyright Laws. No part of this document or any of its contents may be reproduced, copied, modified or adapted, without the prior written consent of the author and DS Environmental.

APPENDIX A: XRF READINGS

Read No.	Room/Area	Wall	Structure	Paint Cond	Substrate	Paint Color	Lead (mg/cm²)	Result
Pre-inspection Calibration							0.0	PASS
Pre-inspection Calibration							0.0	PASS
Pre-inspection Calibration							0.0	PASS
Pre-inspection Calibration							1.0	PASS
Pre-inspection Calibration							1.0	PASS
Pre-inspection Calibration							1.0	PASS

1	Kitchen	B	Wall	Intact	Drywall	White	0.2	Neg
2	Kitchen	*	Ceiling	Intact	Drywall	White	0.2	Neg
3	Kitchen	C	Trim	Intact	Wood	Black	0.0	Neg
4	Kitchen	D	Cabinets	Intact	Wood	Black	0.0	Neg
5	Kitchen	D	Cabinets	Intact	Wood	White	0.0	Neg
6	Living Room	D	Wall	Intact	Drywall	White	0.2	Neg
7	Living Room	*	Ceiling	Intact	Fiberboard	White	0.2	Neg
8	Living Room	*	Ceiling	Intact	Fiberboard	Beige	0.1	Neg
9	Living Room	*	Ceiling	Intact	Fiberboard	Pink	0.2	Neg
10	Living Room	D	Trim	Intact	Wood	Grey	0.2	Neg
11	Kitchen	D	Window Sill	Intact	Wood		0.2	Neg
12	Entry Foyer	A	Wall	Intact	Drywall	White	0.2	Neg
13	Entry Foyer	*	Ceiling	Intact	Drywall	White	0.2	Neg
14	Entry Foyer	A	Trim	Intact	Wood	White	0.1	Neg
15	Entry Foyer	A	Window Sill	Intact	Wood	White	0.2	Neg
16	NE Bedroom	B	Wall	Intact	Drywall	White	0.2	Neg
17	NE Bedroom	*	Ceiling	Intact	Drywall	White	0.2	Neg
18	NE Bedroom	C	Trim	Intact	Wood	White	0.0	Neg
19	NE Bedroom Closet	A	Wall	Intact	Drywall	White	0.2	Neg
20	NE Bedroom Closet	*	Ceiling	Intact	Drywall	White	0.2	Neg
21	NE Bedroom Closet	B	Shelf	Intact	Wood	White	0.1	Neg
22	Hallway	B	Wall	Intact	Drywall	White	0.2	Neg
23	Hallway	*	Ceiling	Intact	Drywall	White	0.2	Neg
24	Hallway	B	Trim	Intact	Wood	White	0.2	Neg
25	Hallway	B	Door	Intact	Wood	White	0.0	Neg
26	Bathroom	B	Wall	Intact	Drywall	Red	0.2	Neg
27	Bathroom	*	Ceiling	Intact	Drywall	Red	0.2	Neg
28	Bathroom	A	Cabinets	Intact	Wood	Red	0.1	Neg
29	Bathroom	B	Window Sill	Intact	Wood	Red	0.2	Neg
30	Bathroom	B	Trim	Intact	Wood	Red	0.2	Neg
31	NW Bedroom	C	Wall	Intact	Drywall	White	0.2	Neg
32	NW Bedroom	*	Ceiling	Intact	Drywall	White	0.2	Neg
33	NW Bedroom	C	Window Sill	Poor	Wood	White	0.2	Neg
34	NW Bedroom	D	Trim	Intact	Wood	White	0.1	Neg
35	NW Bedroom Closet	D	Wall	Intact	Drywall	White	0.2	Neg

36	NW Bedroom Closet	*	Ceiling	Intact	Drywall	White	0.2	Neg
37	NW Bedroom Closet	D	Shelf	Intact	Wood	White	0.2	Neg
38	SE Bedroom	C	Wall	Intact	Drywall	Purple	0.0	Neg
39	SE Bedroom	*	Ceiling	Intact	Drywall	Purple	0.2	Neg
40	SE Bedroom	D	Trim	Intact	Wood	Purple	0.2	Neg
41	SE Bedroom Closet	B	Door	Intact	Wood	Purple	0.1	Neg
42	SE Bedroom Closet	B	Wall	Intact	Drywall	White	0.2	Neg
43	SE Bedroom Closet	*	Ceiling	Intact	Drywall	White	0.2	Neg
44	SE Bedroom Closet	B	Shelf	Intact	Wood	White	0.2	Neg
45	East Entry Foyer	C	Wall	Intact	Drywall	White	0.0	Neg
46	East Entry Foyer	*	Ceiling	Intact	Drywall	White	0.2	Neg
47	East Entry Foyer	B	Trim	Intact	Wood	White	0.2	Neg
48	East Entry Foyer	C	Door/Trim	Intact	Wood	White	0.1	Neg

Post-inspection Calibration	0.0	PASS
Post-inspection Calibration	0.0	PASS
Post-inspection Calibration	0.0	PASS
Post-inspection Calibration	1.0	PASS
Post-inspection Calibration	1.0	PASS
Post-inspection Calibration	1.0	PASS

APPENDIX B: INSPECTOR & FIRM CERTIFICATES

Colorado Department
of Public Health
and Environment

LEAD-BASED PAINT CERTIFICATION*

This certifies that

Chris Lehman

Certification No.: 24948

has met the requirements of 25-7-1104, C.R.S. and Air Quality Control Commission Regulation No. 19, and is hereby certified by the state of Colorado in the following discipline:

Inspector*

Issued: July 15, 2021

Expires: August 27, 2022

* This certificate is valid only with the possession of a valid lead-based paint training certificate in the discipline specified above, issued by either a Colorado approved training provider, an EPA approved training provider, or a training provider approved by another EPA authorized program.

Authorized APCD Representative

SEAL

Inspector Certification: 24948

Colorado Department
of Public Health
and Environment

Lead Evaluation Firm Certificate

This certifies that

DS Environmental Consulting, Inc.

LEF No.: 16918

has met the requirements of 25-7-1104, C.R.S. and Air Quality Control Commission Regulation No. 19, and is hereby certified by the state of Colorado to perform lead-based paint evaluation activities in the state of Colorado.

Issued: January 11, 2022

Expires: January 11, 2023

Authorized APCD Representative

SEAL

Firm Certification: 16918

Certificate of Achievement

This is to certify that

Chris Lehman

DS Environmental Consulting, Inc.

on the 6th of August, 2018 successfully completed the factory training for

Protec Instrument Corporation XRF Lead Paint Inspection System

Including, but not limited to, the topics of Radiation Safety, DOT Regulations, Haz-Mat Security Awareness and the Proper Use of the Instrument.

Vetena Streber, President
Protec Instrument Corporation
38 Edge Hill Road, Waltham, MA 02451

XRF Certification: RMD LPA-1

Certificate of Training

John C. Lehman

Has completed the Heuresis Corp. training materials presented on the topic of Instrument Operator Training, Pb200i, with regards to the materials licensed by the Commonwealth of Massachusetts and the Nuclear Regulatory Commission.

HEURESIS CORPORATION

Instrument Operator Training
Heuresis Corporation, Pb200i

I certify that I have received the stated training and understand the content presented. I understand that I am to conduct this training with questions from Heuresis Corporation.

9/14/2018

Name Date

I confirm that the above named individual has received the training listed on this certificate.

Dillyn Pelletts September 6th 2018

Name Date

XRF Sales, Rentals, Training and Consulting

Title

XRF Certification: Heuresis Pb200i